# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16739/CALL-2

## APPROVED SCHEDULE - B

**EE/BNP/BBMP/E-PMT/10/2014-15, Date: 21.02.2015**

**Improvements and asphalting to Kodigehally enclave roads in Ward no 09 of Vidyaranyapura Sub Division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of B B UMESHA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 726.38 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 80.0 | Rupees Eighty Only |
| 2 | 1952.5 | Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam etc complete as per specifications and directions of engineer in charge of the work | Sqm | 90.0 | Rupees Ninety Only |
| 3 | 376.13 | Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work | Cum | 1500.0 | Rupees One Thousand Five Hundred Only |
| 4 | 3548.5 | Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 14.0 | Rupees Fourteen Only |
| 5 | 3548.5 | Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work | Sqm | 20.0 | Rupees Twenty Only |
| 6 | 95.81 | Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade, etc complete as per specifications and directions of engineer in charge of the work | Cum | 11500.0 | Rupees Eleven Thousand Five Hundred Only |

| | | | | | |
|---|---|---|---|---|---|
| 7 | 690.06 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work | Cum | 80.0 | Rupees Eighty Only |

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**